

Features include:

Quick machine transport and setup.

Integrated debris blower for quick and efficient cuttings removal.

Automated skip cut control for intermittent cut applications.

Extra heavy duty trailer main frame construction.

Low volume water spray system for dust control.

Works on concrete and asphalt.

Cuts both shoulder and center lane rumble strips.

Camera guidance system.

Optional laser guidance system.

Rear view camera to monitor cut quality from truck cab.

Heavy duty truck bed, head ache rack, strobe light bar, 300 gallon water supply tank, adjustable height tow hitch.

Manual skip control to avoid concrete joints.

Oversized engine air cleaner with primary and secondary element. Oversized engine pre-cleaner.

